

## 9. QUANTITATIVO

Estaca		Extensão	Diâmetro	Estaca		Prof. Média + acréscimo	Largura Vala	Movimentação Terra	Escoramento	Embasamento	Movimentação até 1,5m	obs
Montante	Jusante			Montante	Jusante							
0	1	50	160	0,93	2,99	2,060	0,710	73,130	206,000	3,550	53,25	
1	2	50	160	2,99	1,3	2,245	0,710	79,698	224,500	3,550	53,25	
2	3	50	160	1,3	1,26	1,380	0,610	42,090	138,000	3,050	42,09	
3	4	50	160	1,26	1,27	1,365	0,610	41,633	136,500	3,050	41,63	
4	5	50	160	1,27	1,92	1,695	0,610	51,698	169,500	3,050	45,75	
5	6	50	160	1,92	2,16	2,140	0,710	75,970	214,000	3,550	53,25	
6	7	50	160	2,16	2,09	2,225	0,710	78,988	222,500	3,550	53,25	
7	8	50	160	2,09	1,86	2,075	0,710	73,663	207,500	3,550	53,25	
8	9	50	160	1,86	1,27	1,665	0,610	50,783	166,500	3,050	45,75	
9	10	50	160	1,27	1,84	1,655	0,610	50,478	165,500	3,050	45,75	
10	11	50	160	1,84	1,7	1,870	0,610	57,035	187,000	3,050	45,75	
11	12	50	160	1,7	1,51	1,705	0,610	52,003	170,500	3,050	45,75	
12	13	50	160	1,51	1,17	1,440	0,610	43,920	144,000	3,050	43,92	
13	14	50	160	1,17	1,31	1,340	0,610	40,870	134,000	3,050	40,87	
14	15	50	160	1,31	1,45	1,480	0,610	45,140	148,000	3,050	45,14	
15	16	50	160	1,45	2,24	1,945	0,610	59,323	194,500	3,050	45,75	
16	17	50	160	2,24	3,56	3,000	0,710	106,500	300,000	3,550	53,25	
17	18	50	160	3,56	3,39	3,575	0,910	162,663	357,500	4,550	68,25	
18	19	50	160	3,39	2,79	3,190	0,910	145,145	319,000	4,550	68,25	
19	19+9	8,73	160	2,79	2,7	2,845	0,710	17,634	49,674	0,620	9,30	
		<b>958,73</b>						<b>1348,36</b>	<b>3854,67</b>	<b>64,57</b>	<b>953,45</b>	<b>0,00</b>